

API NUMBER 15-135-23,584 -00-00

LEASE NAME #1 Taylor "L"

WELL NUMBER 1

4290' Ft. from S Section Line

1065' Ft. from E Section Line

SEC. 13 TWP. 16S RGE. 25W (E) or (W)

COUNTY Ness

Date Well Completed 7-31-91

Plugging Commenced 7-31-91

Plugging Completed 7-31-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Pickrell Drilling Company, Inc.

ADDRESS 110 N. Market, Suite 205 - Wichita, Ks. 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well D&A ±

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-31-91 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No - Electric Log was not run

Producing Formation None Depth to Top _____ Bottom _____ T.D. 4519'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

8-13-91

AUG 13 1991

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	277' KB	

ON DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged w/50sx @ 1900', 80sx @ 1140', 40sx @ 690', 40sx @ 300', 10sx @ 40' w/bridge plug, 10sx rathole. Plugged w/ 60/40 poz, 6% gel plus 1/4# floeal.per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pickrell Drilling Company, Inc. License No. 5123

Address 110 N. Market, Suite 205 - Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


C. W. Sebitts, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. W. Sebitts

(Address) C. W. Sebitts, President
 110 N. Market, Suite 205

Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 12 day of August, 19 91



Verdella Lewis
 Notary Public

My Commission Expires: 6-06-94

15-135-23584.00.00

PICKRELL DRILLING COMPANY, INC.

110 NORTH MARKET - SUITE 205

WICHITA, KANSAS 67202-1996

(316) 262-8427

#1 Taylor "L"
SW NE NE
Sec. 13-16S-25W
Ness County, Kansas

API: 15-135-23,584
ELEV: 2510' KB, 2508' DF, 2505' GL.
4290' From South line of Section
1065' From East line of Section

- 7-22-91: Prep to spud.
- 7-23-91: (On 7/22) Spud @ 11:30 AM. Set new 20# 8 5/8" casing @ 277'KB, cement w/165sx 60/40 poz. 2%gel 3%CC. Comp. @ 5:00 PM 7/22/91, cement circ. (On 7/23) Drilling @ 1055'.
- 7-24-91: Drlg. @ 2202.
- 7-25-91: Drlg. @ 3111'.
- 7-26-91: Drlg. @ 3620'.
- 7-29-91: (On 7/27) Drlg. @ 4068'. (On 7/28) Drlg. @ 4380'. (On 7/29) Circ. @ 4490'. DST #1 4382'-4430', 30"-60"-30"-30", Rec. 130' Mud, IFP 95#-95#, FFP 95#-95#, ISIP 373#, FSIP 423#.
- 7-30-91: DST #2 4459'-4500, 30"-30"-30"-30", Rec. 20' OCM, IFP 64#-64#, FFP 64#-64#, ISIP 170#, FSIP 114#. DST @4513, packer failure, prep to rerun.
- 7-31-91: Testing @ 4519'. DST #4 4436'-4513', 30"-60"-90"-90", Rec. 165' Drlg. Mud, IFP 45#-45#, FFP 49#-72#, ISIP 1096#, FSIP 1004#.
- 8-01-91: (On 7-31) RTD 4519'. DST #5 4435'-4519', 30"-60"-90"-90", Rec. 140' Thin Drlg. Mud, IFP 45#-49#, FFP 72#-95#, ISIP 1194#, FSIP 1050#. P&A. Plugged w/60/40 poz, 6% gel plus 1/4# floseal per sx, 50sx @ 1900', 80sx @ 1140', 40sx @ 690', 40sx @ 300', 10sx @ 40' w/bridge plug, 15sx rathole. Complete @ 2:00 PM on 7-31-91.

SAMPLE TOPS

T/Anhydrite	1885(+ 625)
B/Anhydrite	1914(+ 596)
Heebner	3850(-1340)
Lansing	3890(-1380)
Stark	4126(-1616)
B/Kansas City	4187(-1677)
Pawnee	4312(-1802)
Fort Scott	4392(-1882)
Cherokee	4418(-1908)
Mississippi	4494(-1984)

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1991

CORPORATION DIVISION
Wichita, Kansas