


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County, Sec. 32 Twp. 16 Rge. 3 (E) W (W)

T - 16 NORTH R - 3W

Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Frank J. Black
Lease Name ~~XXXXXX~~ Erickson Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed July 27, 1964 19
Application for plugging filed July 7, 1964 19
Application for plugging approved July 8, 1964 19
Plugging commenced 7-14-64 19
Plugging completed 7-16-64 19
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	374'2	None
				4-1/2"	3432'	2916'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3435', sanded to 3420' and dumped 4 sacks of cement @ 3420' with dump bailer. Pulled 4 1/2" casing, checked fluid to 225', mudded hole to 210', set rock bridge to 200' and dumped 20 sacks of cement @ 200' with dump bailer. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY License # 436
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of July, 1964

My commission expires May 20, 1968
Milton J. Tolin Notary Public.

15-169-19125-00-00

DONALD J. MELLAND * GEOLOGIST

Phones: CHI-1675 CHI-4582 * Box 783 * McPHERSON, KANSAS

GEOLOGICAL REPORT

Bushart-Termain
Erickson # 1
SW NW SE, Sec. 32-16-3W
Field; Salemsborg
Saline County, Kansas

August 3, 1961
Elevation: 1375 RB est.
Comms: 7/19/61; Comp: 7/27/61
Casing: 8-5/8" = 37 1/2' / 200sx
4-1/2" = 3432' / 90sx

FORMATION TOPS

Mississippian	2925 (-1550)
Kinderhook	3172 (-1797)
Maquoketa Dolomite	3396 (-2021)
RTD	3432 (-2057)

Cores: None

Drill Stem Tests: None

Electrical Logs: None

(All measurements taken from rotary bushing)

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

CONSERVATION DIVISION
Wichita, Kansas

FORMATION SUMMARY

MISSISSIPPIAN

There were no shows of oil within the porous zones of the Mississippian.

MAQUOKETA DOLOMITE

3396 - 3404 Light gray, mottled, leached and sharp chert, poor to fair pin-hole porosity in leached chert, show of free oil, uniform and spotted stain, some included gray, medium crystalline dolomite with poor to fair inter-crystalline porosity, show of free oil, uniform and spotted stain, faint odor. This zone should be located on a gamma-ray-neutron log and tested through perforations.

COPY

15-169-19125-00-00

Wrickson # 1

Geological Report

Page 2

RECOMMENDATIONS

It is recommended that casing be set at a depth of 3432 feet and the Naquoketa Dolomite tested.

Respectfully submitted,

Donald J. Mallard

DJM/z

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

CONSERVATION DIVISION
Wichita, Kansas

C
O
P
Y

15-169-19125-00-00

DRILLING TIME

Bushart-Terman
Ericson # 1

Sec. 32-16-3W
SW NW SE

Elevation: 1375 RB est.
Saline County, Kansas

Depth	Time										Remarks	
2800-2810	2	3	1	2	1	1	1	1	1	1		
20	2	2	1	1	1	2	3	3	3	1		
30	1	3	1	2	3	1	1	1	2	3		
40	2	2	1	2	2	2	2	3	2	1		
50	2	2	2	1	1	1	2	2	2	2		
60	2	1	2	3	2	3	2	2	1	1		
70	2	2	1	1	2	2	1	1	1	1		
80	1	2	4	3	1	1	1	2	1	1		
90	3	2	2	2	2	1	2	2	1	2		
2890-2900	2	1	2	1	1	3	4	3	2	1		
10	2	1	2	4	4	2	1	1	2	1		
20	1	1	1	1	1	1	1	1	1	1		
30	2	3	2	1	2	3	3	3	2	2		
40	2	3	2	3	3	4	3	2	4	4		
50	6	4	3	2	2	2	2	3	4	4		
60	3	3	3	4	3	2	2	1	1	4		
70	3	2	2	2	2	2	2	1	4	2		
80	3	3	2	1	3	1	1	3	4	4		
90	2	5	4	1	1	3	2	2	2	2		
2990-3000	4	4	1	1	2	1	2	9	11	10		
10	15	10	17	16	10	6	2	1	1	1		Tripping 3006'
20	2	4	4	3	3	1	2	4	4	3		
30	2	5	6	3	6	3	2	3	2	3		
40	4	5	4	4	7	3	3	5	6	4		
50	2	2	3	2	2	4	4	9	3	4		
60	5	2	5	3	2	1	2	2	2	2		
70	2	4	3	2	2	1	1	1	2	2		
80	3	2	2	3	3	3	2	2	4	4		
90	2	2	1	3	6	6	4	6	3	3		
3090-3100	4	4	3	4	1	3	3	3	2	5		
10	3	3	4	3	5	8	4	8	5	6		
20	6	6	7	6	8	9	9	10	8	4		
30	5	4	4	4	4	7	8	9	16	8		Tripping 3129'
40	7	6	6	6	3	4	4	5	5	6		
50	6	6	5	6	5	6	6	5	6	6		
60	4	6	6	7	6	6	7	6	5	5		
70	5	3	3	5	5	5	4	5	6	5		
80	4	4	5	5	5	5	7	6	5	6		
90	5	6	5	6	6	4	6	5	6	5		
3190-3200	5	6	5	6	6	5	5	6	5	6		

COPY

Depth	Time										Remarks
3200-3210	5	3	6	6	5	7	4	6	5	5	
20	5	4	6	5	5	5	5	4	5	5	
30	5	5	5	5	5	5	4	5	5	4	
40	3	5	5	4	5	4	4	3	4	4	
50	5	3	4	4	4	4	4	4	4	3	
60	5	3	4	4	4	4	5	4	3	4	
70	3	3	4	4	4	4	4	4	4	4	
80	4	4	4	4	4	3	4	4	3	4	
90	3	4	4	4	4	4	4	4	4	3	
3290-3300	3	4	4	4	3	3	4	4	4	5	
10	3	4	4	4	3	4	4	4	3	4	
20	4	4	4	4	4	4	4	3	4	4	
30	4	4	4	4	4	4	4	4	4	5	
40	5	4	4	4	5	4	4	3	4	5	
50	4	4	4	4	4	4	5	5	4	5	
60	5	5	6	7	7	6	7	7	6	6	
70	7	7	6	6	6	6	6	6	5	4	
80	5	5	5	5	5	6	7	6	7	6	
90	6	6	6	7	7	6	6	6	6	6	
3390-3400	8	9	8	7	7	7	4	4	5	4	Circ. C 3400'
10	4	4	4	4	4	4	4	5	4	4	Circ. S 3406'
20	4	5	5	5	4	4	5	4	4	5	
30	5	6	6	6	6	7	7	7	9	6	
3420-3432	7	9									Circ. 3432'

COPY

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

CONSERVATION DIVISION
Wichita, Kansas