

15-169-00064-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 32 Twp. 16 Rge. (E) 3 (W) C SW SW

Location as "NE/CNW&SW&" or footage from lines

Lease Owner Tom Brown Construction Co.

Lease Name Nelson Well No. 1

Office Address Lindsborg, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed January 23 19 55

Application for plugging filed June 19 66

Application for plugging approved June 29 19 66

Plugging commenced July 15 19 66

Plugging completed July 20 19 66

Reason for abandonment of well or producing formation Insufficient production

If a producing well is abandoned, date of last production May 30 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Maquoketa Dol Depth to top 3373 Bottom Unk Total Depth of Well 3373 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Maquoketa Dolomite	Oil	3373	Unk	5 1/2	3373 1/2	2250

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back to 3360' with gravel. Dumped 5 sacks of cement. Shot pipe off at 2250'. Pulled pipe and mudded hole to 250'. Set rock bridge and dumped 20 sacks of cement, Mudded hole to 40' and dumped 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address Hutchinson, Kans.

STATE OF Kans. COUNTY OF Reno, ss.

Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self

B. R. #4, Hutchinson, Kans.


(Address)

SUBSCRIBED AND SWORN to before me this 24th day of August 19 66

October 18, 1966

My commission expires

Notary Public.



15-169-00064-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


Company- DE WEESE & SANDERSON
Farm- Nelson No. 1

SEC. 32 T. 16 R. 3W
CS/2 S/2 SW

Total Depth. 3379
Comm. 1-13-55 Comp. 1-23-55

County Saline
KANSAS

Shot or Treated.
Contractor. Kiefer & Krause Drlg Co., Inc.
Issued. 3-12-55



CASING:
8 5/8" 340' cem w/250 sx
5 1/2" 3373' cem w/50 sx

Elevation. Est. 1346 D.F.

Production. 25 BO

Figures indicate Bottom of Formations.

surface clay, sand	50
shells, shale	150
red rock, shale, shells	275
shale, shells	340
lime, shale	710
lime	800
lime, shale	1295
shale, shells	1860
lime, shale	2680
lime	2765
shale, lime	2968
lime	3136
lime, shale	3379
Total Depth	RTD

3360

250

Tops:

Mississippi	2913
Kinderhook	3143
Maquoketa Dolomite	3273

Core: None

Drill Stem Tests: #1
3374-79, ep. 1 hr, weak blow
for 12 mins, shut in 20 mins
rec. 25' slightly oil cut mud.
BHP 510# & still building.

Electrical logs: None

All measurements taken from
Rotary bushing.

RECEIVED
OIL CORPORATION COMMISSION
NOV 10 1966
CONSERVATION DIVISION
Wichita, Kansas