


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-169-0479a-00-00
Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

T - 16S NORTH R - 3W



Locate well correctly on above Section Plat

Saline County. Sec. 32 Twp. 16S Rge. 3 (E) W (W)
Location as "NE/CNW&SW" or footage from lines C SE SE
Lease Owner Frank J. Black
Lease Name Peters Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 10-28-61 19
Application for plugging filed 7-7-64 19
Application for plugging approved 7-8-64 19
Plugging commenced 7-16-64 19
Plugging completed 7-22-64 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	322'	None
				4-1/2"	3434'	2933'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3435', sanded to 3420' and dumped 4 sacks of cement @ 3420' with dump bailer. Pulled 4 1/2" casing, bailed fluid to 215', set rock bridge to 200' and dumped 20 sacks of cement @ 200'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY License #436
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 1964

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

W E L L R E C O R D

15-169-04792-00-00

Lease: Peters No. 1

Commenced: 10/20/61

Location: Cen. SE/4 SE/4
Sec. 32-16S-3W
Saline County, Kansas

Completed: 10/28/61

Owner: Bushart-Termain Oil Enterprises, Inc.

Contractor: Melland Drilling Company, Inc.

Casing Record: 8-5/8" @ 322' w/ 286 sacks. 4 1/2" @ 3444' w/ 90 sacks.

FORMATION

LOG

Surface soil, shale & Red Bed	50
Clay, shale & shells	230
Anhydrite	255
Dry drilling	322
Anhydrite	425
Lime & shale	1145
Shale & shells	1620
Lime & shale	2065
Shale	2265
Lime & shale	2702
Shale	2905
Mississippi Lime	3085
Lime	3108
Shale	3359
Shale & lime	3410
Lime	3444

ROTARY TOTAL DEPTH

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1964

CONSERVATION DIVISION
Wichita, Kansas