

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-169-00940-000 Form CP-4

WELL PLUGGING RECORD

NORTH

X			

Locate well correctly on above
Section Plat

Saline County, Sec. ~~27~~ 29 Twp. 16 Rge. 3 (N) (W)
Location as "NE/CNWxSWx" or footage from lines C SW NW
Lease Owner Kiaby Petro. Co.
Lease Name Borg Well No. 1
Office Address 405 1st Nat'l Bank Bldg. Pawhuska, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 12-31-52 19
Application for plugging filed 6-5-67 19
Application for plugging approved 6-6-67 19
Plugging commenced 6-16-67 19
Plugging completed 6-23-67 19
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Maquokota Depth to top 3446 Bottom 3454 Total Depth of Well 3454 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	150'	none
				8 5/8	405'	none
				5 1/8	3446'	3092'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with sand from 3452' to 3425' and dump 5 sacks of cement

Set 15' rock bridge from 315' to 300' and dump 20 sacks of cement

Mud hole to 50', 10' of rock from 50' to 40' and dump 15 sacks of cement to surface

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ronald R. Hamilton

(Address) _____

SUBSCRIBED AND SWORN TO before me this 2 day of August, 19 67

My commission expires Sept. 27, 1967



Notary Public.

15-169-00940-00-00

BORG #1

Operator: National Associated Petroleum Company
Contractor: Stearns Drilling Company
Commencement Date: December 12, 1952
Completion Date: December 31, 1952

Location:
C. SW/4 NW/4
Section 29-16-3,
Saline County, Kansas.

Casing Record:

10 3/4" 155.00 Cemented with 125 sacks.
8 5/8" 408.00 Cemented with 150 sacks.
5 1/2" 3480.33 Cemented with 50 sacks.

WELL LOG

Surface Clay	0	40
Shale and Shells	40	403
Shale and Lime	403	565
Lime	565	970
Shale and Broken Lime	970	990
Shale and Lime	990	2056
Shale	2056	2260
Shale and Lime	2260	2320
Lime	2320	2365
Shale and Lime	2365	2762
Shale	2762	2960
Lime	2960	3210
Lime and Shale	3210	3275
Shale and Shells	3275	3405
Lime and Shale	3405	3454
Total Depth:	3454	

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1953
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.



SUBSCRIBED AND SWORN to before me this 5th day of January, 1953.


Notary Public

My Commission Expires: June 20, 1953

