

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-169-00942-80-00 Form CP-4
WELL PLUGGING RECORD

Saline County, Sec. 29 Twp. 16 Rge. 3 (E) (W)

Location as "NE/CNW/SW" or footage from lines. C SE NW
Lease Owner Kirby Petro. Co.
Lease Name Varnlof Well No. 2
Office Address 402 1st Nat'l Bank Bldg. Pawhuska, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 12-4-57 19
Application for plugging filed 6-5-67 19
Application for plugging approved 6-6-67 19
Plugging commenced 6-26-67 19
Plugging completed 6-28-67 19
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Sylvan Dolomite Depth to top 3416 Bottom 3424 Total Depth of Well 3424 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	177	none
				5 1/2	3416'	2830'

- Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with chat from 3426' to 3400' and dump 5 sacks of cement

Set 10' rock bridge from 210' to 200' and dump 35 sacks of cement

Mud hole to 25', rock from 25' to 20' and dump 10 sacks of cement to surface

ACID 07-03-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Ronald L. Hanson*

(Address)


SUBSCRIBED AND SWORN to before me this 2 day of August, 19 67

My commission expires

Sept. 27, 1967

Ronald L. Hanson

Notary Public.



TOKLAN OIL CORPORATION, Owner

L.B. Jackson Drilling Co.
Contractor.

15-169-00942-00-00

Varnlof #2

C SE NW Sec 29-16S-3W
Saline County, Kansas

Total Depth 3424'
Commenced 11-20-57
Completed 12-4-57

Elevation 1584' DF

Casing

10 3/4" Set at 177' Cemented w/180 sacks circulated to surface.
5 1/2" Set @ 5416' Cemented w/125 sacks.

<u>Formation</u>	<u>From</u>	<u>To</u>
Shale & Sand	0	192
Shale & Shells	192	575
Shale & Lime	575	708
Shale & Lime Shells	708	880
Shale & Lime	880	1145
Lime	1145	1170
Shale & Lime	1170	1200
Lime	1200	1339
Shale	1339	1675
Shale & Lime	1675	1985
Lime	1985	2080
Lime & Shale	2080	2125
Shale	2125	2191
Shale & Lime	2191	2350
Lime	2350	2380
Shale & Lime	2380	2625
Lime	2625	2642
Lime & Shale	2642	2995
Lime	2995	3188
Shale	3188	3417
Shale & Lime	3417	3421
Shale & Lime	3421	3424

<u>Tops:</u> Lansing Lime	2277 (- 918)
Mississippi Chat	2982 (-1573)
Mississippi Lime	3147 (1768)
Woodford Shale	3190 (-1811)
Sylvan Shale	3386 (-2007)
Sylvan Dolomite	3414 (-2035)

STATE OF KANSAS)
) ss
COUNTY OF SALINE)

I hereby certify that the above is correct to the best of my knowledge.

By Ray Campbell
L. B. JACKSON DRILLING COMPANY

Subscribed and sworn to before me this 27 day of December, 1957.

Gene L. Larson
Notary Public

My commission expires

December 1, 1960

Original and one copy filed
with Kansas Corporation Commission

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1957
CONSERVATION DIVISION
Wichita, Kansas