


15-169-19141-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail of Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Salina County, Sec. 20 Twp. 16 Rge. 3 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Leonard Bruce
Lease Name Anna Johnson Well No. I
Office Address Rt. 1 McPherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 5-16 19 61
Application for plugging filed 9-19 19 72
Application for plugging approved 9-20 19 72
Plugging commenced 9-25 19 72
Plugging completed 9-29 19 72
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Gilbert Tomar

Name of Conservation Agent who supervised plugging of this well Gilbert Tomar
Producing formation Depth to top Bottom Total Depth of Well 3506' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,849'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3506' to 3490'. Dumped 3 ax of cement. Mudded hole to 260'. Made 15' of rack bridge. Dumped 3 1/2 Yrds of Ready-Mix cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1972
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September 19 72

My commission expires January 5, 1974



Judy Lamb
Notary Public.

15-169-19141-00-00

DONALD J. MELLAND * GEOLOGIST
PHONES: 720-1908 * BOX 783 * McPHERSON, KANSAS

GEOLOGICAL REPORT

Bushart-Forman
Amos Johnson #1
2000 W. St., Sec. 20-16-31
Field: Waldenborg
Saline County, Kansas

May 17, 1961
Elevation: 1300 RB
Core: 5/3/61; Comp: 5/16/61
Casing: 2-5/8" x 11.7' / 212px
1-1/2" x 350' / 60ax

80 pgs

FORM III - 1958

Mississippian	2940 (-1522)
Kinderhook	3185 (-1727)
Wagonketa Dolomite	3422 (-2034)
Viola	3483 (-2095)
Top	3506 (-2117)

Cores: None

Drill Stem Tests: None

Electrical Logs: None

(All measurements taken from rotary busting)

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1972
CONSERVATION DIVISION
Topeka, Kansas

ROCK LOG SUMMARY

MISSISSIPPIAN

There were no shows of oil within the porous zones of the Mississippian.

WAGONKETA DOLOMITE

3422-3430 Light gray, mottled, fossiliferous, sharp and leached chert, small amount of leached chert with poor pinhole porosity, show of free oil, light spotted stain, small amount of included gray medium crystalline dolomite with poor pinhole porosity, slight show of free oil, rare spotted stain, faint odor in wet sample. This zone should be located on a gamma ray-neutron log and tested through perforations.

COPY