

15-169-00596-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Saline County. Sec. 20 Twp. 16 Rge. 3 (E) (W)
Location as "NE/CNW&SW" or footage from lines. C NE SW SW
Lease Owner Kirby Petro. Co.
Lease Name Swenson C Well No. 2
Office Address 402 1st nat'l Bank Bldg. Pawhuska, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 6-29-53 19
Application for plugging filed 6-5-67 19
Application for plugging approved 6-6-67 19
Plugging commenced 7-14-67 19
Plugging completed 7-19-67 19
Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Maquoketa Depth to top 3455 Bottom 3456 Total Depth of Well 3456 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	159	none
				8 5/8	416'	49.88
				5 1/2	3455'	3790

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with chat from 3456' to 3420' and dump 5 sacks of cement

Set 10' rock bridge from 285' to 275' and dump 25 sacks of cement

Pull 50' of 8 5/8" pipe

Mud hole to 30', rock to 30' to 20' and dump 15 sacks of cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1967

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

CONSERVATION DIVISION
WICHITA, KANSAS


STATE OF Kansas, COUNTY OF Butler, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Handwritten Signature]*

(Address) _____, 19 67

[Handwritten Signature]
Notary Public.

SUBSCRIBED AND SWORN TO before me this 2 day of August, 1967.
My commission expires Sept. 27, 1967



15-169-00596-00-00

NATIONAL ASSOCIATED PETROLEUM COMPANY
SWINSON NO. C-2
SALINE COUNTY, KANSAS

Drilling Contractor: Exploration Drilling Co.
220 North Boston
Tulsa, Oklahoma

Started Rigging Up : 6-12-53
Started Drilling : 6-13-53
Completed Drilling : 6-29-53

Set: 5 Joints of 10-3/4" Surface Casing
@ 159' W/125 Sacks of Cement.

Set: 98 Joints of 5-1/2"
Casing @ 3455' W/100
Sacks of Cement.

Set: 13 Joints of 8-5/8" Intermediate
Casing @ 416' W/100 Sacks of Cement.

FORMATIONS

Surface	0'	161'
Shale & Sand W/Lime Strks.	161	409
Sand & Shale	409	530
Lime & Shale	530	720
Lime	720	973
Sand & Shale	973	1054
Shale	1054	1450
Shale & Shells	1450	1580
Lime & Shale	1580	2060
Lime	2060	2150
Lime & Shale	2150	2470
Lime	2470	2835
Lime & Shale	2835	2952
Shale W/Sand & Lime	2952	3000
Lime & Chert	3000	3072
Lime	3072	3131
Lime, Chert & Shale	3131	3165
Lime & Shale	3165	3185
Lime	3185	3220
Lime & Shale	3220	3326
Shale	3326	3455
Dolomite	3455	3455 Total Depth

RECEIVED
STATE DEPARTMENT OF CONSERVATION
JUN 6 1967
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

This is to certify that the above and foregoing is a true, correct, and complete copy of the Driller's Log covering the Swinson No. C-2 according to the records of this office and the best of my knowledge and belief.

EXPLORATION DRILLING COMPANY

Gloria M. Kee

W. H. Lewis
Notary Public

Subscribed and sworn to before me this 14th day of July, 1953.

My commission expires April 25, 1954.