


15-169-00007-00-00 GP

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 20 Twp. 16 Rge. 3W (E4) (W)
Location as "NE/CNW&SW" or footage from lines. NE NE SW
Lease Owner Kirby Petroleum Co.
Lease Name Nelson Well No. 1
Office Address 402 1st Nat'l Bank Bldg. Pawhuska, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 5-24-52 19__
Application for plugging filed 6-5-67 19__
Application for plugging approved 6-6-67 19__
Plugging commenced 8-3-67 19__
Plugging completed 8-7-67 19__
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Maquoketa Depth to top 3427 Bottom 3436 Total Depth of Well 3436 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	335	0
				5 1/2	3426 7	2933.91

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with chat from 3436' to 3410' and dump 5 sacks cement

Set bridge at 265' and dump 25 sacks cement, mud hole to 35', set 5' rock bridge and dump 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss. _____
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Davis

SUBSCRIBED AND SWORN TO before me this 21 day of August, 19 67

Ronald R. Hanson

Notary Public.

My commission expires Sept. 27, 1967

ROTARY DRILLER'S LOG

15-169-00007-00-00

National Associated Petroleum Company
502 Ritz Building
Tulsa, Oklahoma

Elevation: 1395 K. B.

8-5/8" x 5 1/2" Head 6.45'
below K. B.

Nelson #1

Casing Record:

NE/4 NE/4 SW/4
Sec. 20-16-3W
Saline County, Kansas

8-5/8" Csg. 335' w/215 sx.

5-1/2" Csg. 3426'7" w/75 sx.
5-1/2" casing set 10' off
bottom.

Well Commenced: 5- 6-52
Well Completed: 5-24-52

Recemented 8-5/8" w/90 sacks
May 14, 1952.

Contractor: E. K. Carey Contractor (Rig #2) Box 620, McPherson, Kansas
Geologist: Bill Clark, National Associated Pet. Company.

Figures Indicate Bottom of Formation K. B.

Cellar	8
Clay & shale	50
Sand	57
Shale	90
Shale & shells	290
Sand	295
Lime & shale	335
Lime & shale	1075
Shale & shells	1675
Lime & shale	2100
Shale & lime	2297
Lime (K. C.)	2313
Lime	2615
Lime & shale	2647
Lime	2664
Shale & lime	2878
Shale & shells	2947
Lime (Miss.)	2960
Lime	3221
Shale & lime	3330
Shale	3426
Lime	3436'7" T.D.

D. S. T. 3430 to ^{36-7"}37', tool open
2 hours, recovered 37' oil cut
mud - 15 min. BHP 135#

RECEIVED
STATE COMMISSION
JUN 6 1952
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED

MAY 28 1952

NATL ASSOC. PET. CO.

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

E. K. CAREY CONTRACTOR

By Herbert Rhoton
Herbert Rhoton, Superintendent