

15-169-00234-00-00

FORM - CP-2  
Rev. 6-26-62

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 25, 1964

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Gail Metz of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Metz guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: 502 Ritz. Bldg., Tulsa, Oklahoma

Lease Name: Bergland Well No. 1

Location: NW NW NW Sec. 31 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3787' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Metz was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and cement with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/4 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,  
*Arthur J. Loman*