

State of Kansas



15-169-00606-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

August 1, 1967

RECEIVED  
STATE CORPORATION COMMISSION

AUG 8 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Smith of Flint Eng. & Constr. Co. has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Kirby Petroleum Company

Complete Address: 402 First Nat'l Bank Bldg., Pawhuska, Okla. 74056

Lease Name: Varnlof Well No. 1

Location: C NE NW Sec. 29 Twp. 16 Rge. 3 (E) (W) X

County Saline Total Depth 3420' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Smith was instructed to plug the well as follows:


Fill hole with sand to 3400' and cement with 5 sacks.

Fill hole with mud to 275'. Set rock bridge from 275' to 265' and

cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent