

State of Kansas



15-169-00603-00-011

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

January 31, 1968

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 1 1 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Jim Beakey of Lynch Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Beakey guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: Box 150, Mc Pherson, Kansas 67460

Lease Name: Lindshield "A" Well No. 2

Location: C SE SW Sec. 29 Twp. 16 Rge. 3 (E)(W) X

County: Saline Total Depth 3456' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Beakey was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 5 sacks cement.

Fill hole with mud to 250'. Set rock bridge from 250' to 240' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent