

State of Kansas



15-169-00602-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg.  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 3 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

February 6, 1969

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Jim Beakey of Ralph Lynch Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: P.O. Box 150, Mc Pherson, Kansas 67460

Lease Name: Lindshield "A" Well No. 1

Location: C NE SW Sec. 29 Twp. 16 Rge. 3 (E) (W) X


County: Saline Total Depth 3465' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Beakey was instructed to plug the well as follows:

- Fill hole with sand to 3450' and cement with 5 sacks cement.
- Fill hole with mud to 250'. Set rock bridge from 240' to 250' and
- cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock
- bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent