

State of Kansas



15-169-19136-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent).

December 17, 1966

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this  
date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: W-D Oil Company (Box 296, Burlington, Colo.)  
c/o Bert Self

Complete Address: R. R. #4, Hutchinson, Kansas

Lease Name: Lunquist "B" Well No. 2

Location: NW NE NW Sec. 27 Twp. 16 Rge. 3 (E)(W) X

County Saline Total Depth 3402' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3380' and cement with 5 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent