

State of Kansas



15-169-00174-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Main  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JAN 17 1967

January 6, 1967  
CONSERVATION DIVISION  
Wichita, Kansas

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: W-D Oil Company (Box 296, Burlington, Colorado)  
c/o Bert Self

Complete Address: R.R. #4, Hutchinson, Kansas

Lease Name: Lundquist Well No. 1

Location: NE NW NW Sec. 27 Twp. 16 Rge. 3 (E)(W) X

County Saline Total Depth 3331' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

- Fill hole with sand to 3300' and cement with 5 sacks.
- Fill hole with mud to 310'. Set rock bridge from 310' to 300' and cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

*[Signature]*  
Conservation Division Agent