

State of Kansas



15-169-00596-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 15, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Troy Smith of Flint Eng. & Constr. Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Kirby Petroleum Company

Complete Address: 402 First Nat'l Bank Bldg., Pawhuska, Okla. 74056

Lease Name: Swenson "C" Well No. 2

Location: C SW SW Sec. 20 Twp. 16 Rge. 3 (K) (W) X

County Saline Total Depth 3459' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 3425' and cement with 5 sacks.

Fill hole with mud to 285'. Set rock bridge from 285' to 275' and

cement hole with 25 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

RECEIVED

STATE CORPORATION COMMISSION

JUL 20 1967

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

[Signature]
Conservation Division Agent