

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1973

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cain of Strata Drlg. has this
date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Co.

Complete Address: 1130 Vickers KSB&T Bldg., Wichita, Ks.

Lease Name: North Well No. 2

Location: NE NW SW Sec. 1 Twp. 16 Rge. (E)(W) 25

County: Ness Total Depth 4506' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cain was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 800' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Bio F. Massey
Conservation Division Agent