

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Abercrombie Drlg. has this
date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Vincent Oil Corporation

Complete Address: 719 Union Center Bldg., Wichita, Ks.

Lease Name: Huxman Well No. 1

Location: C E/2 NE Sec. 15 Twp. 16 Rge. (E)(W) 25

County: Ness Total Depth 4543' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weber was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
60 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. J. Massey
Conservation Division Agent