

52-040580

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

15-169-04768-00-00

API NUMBER: N/A
S/2 SE, SECTION 29 TOWNSHIP 16 RANGE 3W

OPERATOR LICENSE # 5374 1320 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE

OPERATOR CAP Operating, Inc.
NAME & RR #2, Box 87A
ADDRESS Galva, KS 67403

LEASE NAME: Nordling "B" #1
COUNTY: Saline
WELL TOTAL DEPTH: 3441' 111.83

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 385'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: PERF e 3410'

PLUGGING CONTRACTOR: CAP
ADDRESS: _____ LICENSE: 5374

COMPANY TO PLUG AT: HOUR: 3:00 DAY: 12 MONTH: 12 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Dennis Casebeer
COMPANY NAME: CAP PHONE: 316-654-3747

WERE: Sand to 2400' - c/w/4 sx cmt - bail hole dry to 325' -
set S.B. - redimix to surface - cut 5-1/2" down inside
of 8-5/8" so annulus will fill w/cmt.

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 4:00p DAY: 13 MONTH: 12 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded to 2400' - c/w/4 sx - bailed hole dry to 325'
set SB - redimixed to surface - cut 5-1/2" down inside
of 8-5/8" so annulus would fill w/cmt - used 4 Yds
redimix - McPherson Concerte.

REMARKS: _____

I DID OBSERVE THIS PLUGGING.

INVOICED

Ralph Tittel
Ralph Tittel

DEC 26 1990

CONSERVATION DIVISION
FORM ICR-2/3
Wichita, Kansas
REV. 3/90

DATE 1-8-91

INV. NO. 30406

12-13

ow