

1 070182

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,026 -00-00  
NE NW SE, SEC. 4, T 16 S, R 25 (W) ~~E~~  
2310 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039  
Operator: L. D. Drilling, Inc.  
Name & Address: R. R. 1, Box 183-B  
Great Bend, KS 67530

Lease Name Carter Well # 1  
County Ness 146.54  
Well Total Depth 4509 Mississippi feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co., Inc. License Number 5929  
Address Box 823, Great Bend, KS 67530

Company to plug at: Hour: 10:30 pm Day: 12 Month: May Year: 19 86

Plugging proposal received from Ervin Neighbors

(company name) Duke (phone) 316-793-8366

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2519'  
Anhydrite 1930'

1st plug at the base of the Anhydrite with 40 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug at 380' with 50 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement  
Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:15 am Day: 12 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1960' with 40 sx cement, 2nd plug at 1200' with 80 sx cement, 3rd plug at 400' with 50 sx cement, 4th plug from 40' to surface with 10 sx cement  
5th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAY 19 1986

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

INVOICED (do not observe this plugging.)

DATE MAY 20 1986

Signed Dan Goodnow (TECHNICIAN)

INV. NO. 13933

(see rules on reverse side)

Starting Date May 3, 1986 month day year

API Number 15- 135-23,026-0000

OPERATOR: License # 6039
Name L. D. Drilling, Inc.
Address Route 1, Box 183-B
City/State/Zip Great Bend, KS 67530
Contact Person L. D. Davis
Phone 316-793-3051

NE NW SE Sec. 4 Twp. 16 S, Rg. 25 East
2310 West
1650 Ft. from South Line of Section
Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5929
Name Duke Drilling Co., Inc.
City/State Wichita, KS 67202

Nearest lease or unit boundary line 330 feet
County Ness
Lease Name Carter Well # 1
Ground surface elevation 2525' (estimate) feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 100'
Depth to bottom of usable water 1150'
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 350'
Conductor pipe required
Projected Total Depth 4525 feet
Formation Miss.

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date Signature of Operator or Agent J. M. Vess Title

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X D
This Authorization Expires 11-2-86 Approved By [Signature]

set 350' at 8 5/8
Will Plug Early Morning 5-17

NE NW SE Sec. 4 Twp. 16 S, Rg. 25 East
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, Formation, Depth with, and SXS of. Includes handwritten entries for 1st plug @ 4500, 2nd plug @ 1900, 3rd plug @ 1200, 4th plug @ 380, 5th plug @ 40, and (2) Rathole with 15.

Vertical list of fields for well completion: PUSHER, TD, FORMATION, SURFACE PIPE @, ANHYDRITE, ELEVATION, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/, 2nd PLUG @ FT. W/, 3rd PLUG @ FT. W/, 4th PLUG @ FT. W/, RAT HOLE CIRCULATED W/, MOUSE HOLE CIRCULATED W/, WATER WELL PLUGGED W/, CEMENT COMPANY, TECHNICIAN.

Handwritten signature or initials.