

1 060805

267 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,005-60-00
100' W of
NE NW , SEC. 4, T 16 S, R 25 W/EX
4620 feet from S section line
3400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Carter Well # 1-H

Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Suite 205
Wichita, KS 67202

County Ness 145.60
Well Total Depth 4480 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 329 KB

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 15 Month: February Year: 19 86

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone) 316-262-8427
Elevation 2475GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1895-1931'
1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:15 pm Day: 15 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1931' with 50 sx cement, 2nd plug at 1305' with 80
sx cement, 3rd plug at 370' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15
sx cement.

Remarks: Used 60/40 Pozmix 4% gel 2% cc by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 27 1986

INV. NO. 12713

observe this plugging, RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthi
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 2 10 86 month day year

API Number 15- 135-23,005-0000
100' W of NE NW Sec. 4 Twp. 16 S, Rg. 25 East
4620 Ft. from South Line of Section
3400 Ft. from East Line of Section

OPERATOR: License # 5123
Name Pickrell Drilling Company, Inc.
Address 110 N. Market, Suite 205
City/State/Zip Wichita, Kansas 67202
Contact Person Jay McNeil
Phone 262-8427

Nearest lease or unit boundary line 660 feet
County Ness
Lease Name Carter Well # 1-H
Ground surface elevation
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 60
Depth to bottom of usable water 200-250
Surface pipe planned to be set 300'+
Projected Total Depth 4550 feet
Formation Mississippi

CONTRACTOR: License # 5123
Name Pickrell Drilling Company, Inc.
City/State Wichita, Kansas
Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
cementing will be done immediately upon setting production casing.
Date 2-3-86 Signature of Operator or Agent Title Chief Geologist

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per AL 2
This Authorization Expires 8-3-86 Approved By

Move in 2-7-86 set 330' of 8 1/8" no

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, casing size, and material. Includes entries for 1st plug @ 1900 feet depth with 50 60/40 poz. 4%gel 2%CC, 2nd plug @ 1000 feet depth with 80, 3rd plug @ 350 feet depth with 40, 4th plug @ 40' w/solid bridg plug 10, 5th plug @, and (2) Rathole with.

Handwritten notes: PUSHED Gary Christopher, TD 4480 FORMATION MIX, SURFACE PIPE 8 5/8 @ 329' HB, ANHYDRITE 1896 ELEVATION 2475, STARTING TIME & DATE 2-15-86 3:00 PM, COMPLETION TIME & DATE 2-15-86 5:16 PM, 1st PLUG @ 193 FT. W/ 50 SX, 2nd PLUG @ 1305 FT. W/ 80 SX, 3rd PLUG @ 370 FT. W/ 40 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANIED 6/4 49220

TECHNICIAN, RECEIVED STATE CORPORATION COMMISSION, FEB 24 1986, CONSERVATION DIVISION Wichita, Kansas