

1 060917

DEC 29 1986

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,084-00-00

SE NW SW, SEC. 12, T 16 S, R 25 W/E X

1650 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7076

Lease Name Giess Well # 1

Operator: Black Diamond Oil, Inc.

County Ness 147.55

Name & Address 1105 East 30th, Suite A

Well Total Depth 4540 feet

Hays, KS 67601

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor R & C Drilling Company Inc. License Number 9087

Address P.O. Box 296, Hays, KS 67601

Company to plug at: Hour: 8 p.m. Day: 28 Month: 12 Year: 19 86

Plugging proposal received from John Weis

(company name) R & C Drilling Company Inc. (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe. Elevation 2543' GL  
Anhydrite 1932-65'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at Base Cheyenne with 100 sx cement,

3rd plug at 30' below base of surface pipe with 50 sx cement, 4th plug at 40-0' with 10

sx cement, 5th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 12:15 a.m. Day: 29 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1960' with 50 sx cement,

2nd plug at 1150' with 100 sx cement,

3rd plug at 250' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION  
12-31-86  
DEC 31 1986

CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

did not observe this plugging.

DATE 1-5-87

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 15745

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12-12-86 month day year

API Number 15-135-23,084-00-00

OPERATOR: License # 7076 Name BLACK DIAMOND OIL, INC. Address 1105 East 30TH, SUITE A City/State/Zip HAYS, KS 67601 Contact Person KENNETH Vehige Phone 913.625-5891

SE NW SW Sec. 12 Twp. 16 S, Rg. 25 East X West 1650 Ft. from South Line of Section 4290 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 990 feet County NESS

CONTRACTOR: License # 9087 Name R. & C. DRILLING CO. INC City/State HAYS, KS

Lease Name GJESS Well # 1 Ground surface elevation 2543 feet MSL

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows:

Depth to bottom of fresh water 150 Depth to bottom of usable water 850/1150

Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1-2 X Surface pipe planned to be set 200 feet

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Conductor pipe required Projected Total Depth 4500 feet Formation Mississippi

Date 12-5-86 Signature of Operator or Agent Kenneth Vehige Title Owner/Operator

For KCC Use:

Formation Mississippi

Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 400 feet per Alt.

This Authorization Expires 6-10-87 Approved By 12-10-86

SPUD-12-15-86

set 200' of 85/8"

Signature

SE NW SW Sec. 12 Twp. 16 S, Rg. 25 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1660 feet depth with 20 sks of 50/50 Poz. 6% Gel
2nd plug @ 910 feet depth with 1 flow seal-100 sks of 50/50 Poz. 6% Gel
3rd plug @ 250 feet depth with 40 sks of 50/50 Poz. 6% Gel
4th plug @ 40 feet depth with solid bridge plug and 10 sks of 50/50 Poz. 6% Gel
5th plug @ feet depth with sks of
(2) Rathole with 10-50/50 sks and 1 sks hulls (b) Mousehole with sks

Base any 50 lb Bull Charge 100 lbs 60/40 w/6%

PUSHER John Well TD 4540 FORMATION Mississippi SURFACE PIPE 8 1/2 @ 222 ANHYDRITE 1965 ELEVATION 2543 94 8 PM STARTING TIME & DATE 12-28 COMPLETION TIME & DATE 12-15 AM 12-29 1st PLUG @ 1960 FT. W/ 50 SX 2nd PLUG @ 1150 FT. W/ 100 SX 3rd PLUG @ 250 FT. W/ 50 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ 60/40 6% CEMENT COMPANY Allied TECHNICIAN J.A.P.

12-31-86 STATE CORPORATION COMMISSION DEC 31 1986 CONSERVATION DIVISION Wichita, Kansas