

1 060039

10-3

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,508-00-00

SW SE NW, SEC. 5, T 16 S, R 25 W/E

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4689

Lease Name Evel "F" Well # 1

Operator: Thomas C. Lutz

County Ness 144.72

Name & Address P.O. Drawer 0940

Well Total Depth 4453 feet

Fayetteville, AR 72701

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 383

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Bldg. Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 2 Month: 10 Year: 19 90

Plugging proposal received from Walt Oden

(company name) Red Tiger Drilling Company (phone) 316-263-2371

Elevation 2484'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1939-74'

1st plug at 1980' with 50 sx cement, 2nd plug at 1090' with 80 sx cement,

3rd plug at 410' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 2 a.m. Day: 3 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1980' with 50 sx cement,

2nd plug at 1090' with 80 sx cement,

3rd plug at 410' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 8 1990

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton. (If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

INVOICED

DATE 10-19-90

Signed Case Morris (TECHNICIAN)

BY: 29667

10-3

JAN 10 1991

EFFECTIVE DATE: 9-29-90

P.U.

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas

FORM MUST BE SIGNED

NOTICE OF INTENTION TO DRILL 135-23,508-00-00 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... September 30 ... 1990 ...  
month day year

.SW. SE. NW... Sec .5... Twp .16. S, Rg 25. X West

OPERATOR: License # 4689  
Name: Thomas C. Iutz  
Address: P.O. Drawer 0940  
City/State/Zip: Fayetteville, AR 72701  
Contact Person: H. L. Maddox  
Phone: 316-653-4178

2970 feet from South line of Section  
3630 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5302  
Name: Red Tiger Drilling Co.

County: Ness  
Lease Name: Evel "F" Well #: 1  
Field Name: Arnold  
Is this a Prorated Field? ... yes X... no  
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 1650  
Ground Surface Elevation: 2484 feet MSL  
Domestic well within 330 feet: ... yes X... no  
Municipal well within one mile: ... yes X... no  
Depth to bottom of fresh water: 100  
Depth to bottom of usable water: 1100  
Surface Pipe by Alternate: ... 1 X... 2  
Length of Surface Pipe Planned to be set: 350  
Length of Conductor pipe required: N/A  
Projected Total Depth: 4650  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well X... farm pond ... other

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal X Wildcat ... Cable  
... Seismic; ... # of Holes

If OWWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes X... no  
If yes, total depth location: \_\_\_\_\_

DWR Permit #: N/A  
Will Cores Be Taken?: ... yes X... no  
If yes, proposed zone: \_\_\_\_\_

AFFIDAVIT

250' Alt. II Req.

Exp. 3/24/91

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Walt Odey INIT. DG  
 SPUD DATE 9-25-90 LENGTH SURFACE PLANNED 350  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect. bbls. when done bbls.  
 RATHOLED AHEAD? Y N SIZE HOLE  
 SURFACE PIPE 1 7/8 @ 223 CONDUCTOR  
 ANHYDRITE T- 1931 B- 1974 ELEVATION 2484  
 TD 4453 FORMATION \_\_\_\_\_  
 RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
 \_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_  
 \_\_\_\_\_ Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 \_\_\_\_\_ Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 \_\_\_\_\_ Anhydrite Base @ 1280 Ft. W/ 50 SX  
 \_\_\_\_\_ 1/2 Base Anyh. @ 1090 Ft. W/ 80 SX  
 \_\_\_\_\_ 1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 Bottom Surface @ 710 Ft. W/ 50 SX  
 \_\_\_\_\_ @ 450 Ft. W/ 10 SX  
 RAT HOLE CIRCUMFERENCE \_\_\_\_\_  
 WATER WELL \_\_\_\_\_  
 TECHNICAL DIVISION \_\_\_\_\_  
 WICHITA, KANSAS  
 TYPE OF CEMENT 60/40 Poz 6% 1/4 # Fibers  
 STARTING TIME 11: \_\_\_\_\_ (AM/PM) DATE 10-2-90  
 COMPLETION TIME 2: \_\_\_\_\_ (AM/PM) DATE 10-3  
 CEMENT COMPANY Adel