

1060001

7-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,686-00-00

SW SW NE, SEC. 13, T 16 S, R 25 W/R

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Marjorie Well # 1

Operator: Beren Corporation

County Ness 146.38

Name & Address Box 723

Well Total Depth 4504 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Beren Corporation License Number 5364

Address Box 723, Hays, KS 67601

Company to plug at: Hour: 10:30 a.m. Day: 7 Month: 7 Year: 19 89

Plugging proposal received from Bob Grant

(company name) Beren Corporation (phone) 913-628-6101

were: 4 1/2" at 4497' Open hole 2-staged Anhydrite to 0' with 500 sx cement

1st plug pump 600 lbs. hulls and 150 sx light cement.

Plugging Proposal Received by Dan Goodorw
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:50 a.m. Day: 7 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 600 lbs. hulls and 200 sx cement. Pumping pressure 0-1100 psi and shut in 850 psi.

2nd plug pumped in between 8 5/8" & 4 1/2" casing with 40 sx cement.

Pumping pressure 0-500 psi and shut in 350 psi.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1989
7-11-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used Thrifty Mix cement by B.J. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 7-13-89

Signed [Signature]
(TECHNICIAN)

INV. NO. 25322