

1 070972

8-25

265R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,587-00-00

NW SW SW, SEC. 18, T. 16 S, R. 25 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4689

Lease Name Evel-X Well # 1

Operator: Thomas C. Lutz
Name & Address: 1666 Halsell
Fayetteville, AR 72701

County Ness 148.20

Well Total Depth 4560 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KSB & T Bldg., Wichita, KS 67202

Company to plug at: Hour: 10:30 p.m. Day: 24 Month: 8 Year: 19 91

Plugging proposal received from Walt Oden

(company name) Red Tiger Drilling Company (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1965-95'
1st plug at 2000' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,
3rd plug at 280' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4 a.m. Day: 25 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2000' with 50 sx cement,

2nd plug at 1200' with 80 sx cement,

3rd plug at 280' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

AUG 27 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.

(If additional description is necessary, use BACK of this form.)

INVOICED

(Check box if not observed) observe this plugging.

DATE SEP 06 1991

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 32972

8-25 NOV 20 1991

EFFECTIVE DATE: 7-31-91

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL

135-23587-00-00 FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 1 1991
month day year

NW..SW..SW Sec ..18 Twp 16.. S, Rg .25. East
 West

OPERATOR: License # 4689
Name: Thomas C. Lutz
Address: 1666 Halsell
City/State/Zip: Fayetteville, Ar 72701
Contact Person: H.L. Maddox
Phone: 316-653-4178

990 feet from South line of Section
4950 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 8241
Name: ~~Emphasis Oil Operations~~ Red Tiger
Rig # 5

County: Ness
Lease Name: Evel-X Well #: 1
Field Name: Arnold

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj Infield .. Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 330
Ground Surface Elevation: NA feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 150
Depth to bottom of usable water: 1175
Surface Pipe by Alternate: ... 1 2

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Length of Surface Pipe Planned to be set: 250 ft.
Length of conductor pipe required: 0
Projected Total Depth: 4650
Formation at Total Depth: 4600

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location:
Expires 1-26-92

Water Source for Drilling Operations:
... well farm pond ... other
DWR Permit #:
Wild Caves Be Taken? ... yes no
If yes, Wild Caves zone:

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Walt Oden

SPUD DATE 8-16-91 INIT. S.P.

LENGTH SURFACE PLANNED 250' of 8 1/2"

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. ___ bbls. ___ when done ___ bbls.

RATHOLED AHEAD? Y ___ N ___ SIZE HOLE
SURFACE PIPE 8 1/2" @ 258 CONDUCTOR
ANHYDRITE T- 1965 B- 1995 ELEVATION

TD 4560 FORMATION

RAN PIPE @ ___ DV TOOL ___ ALT II DONE ___
SX ___ Y ___ N ___

Arbuckle Plug @ ___ Ft. W/ ___ SX
Hug./Council @ ___ Ft. W/ ___ SX
Anhydrite Base @ 2000 Ft. W/ 50 SX
1/2 Base Anyh. @ 200 Ft. W/ 80 SX
1/2, 1/2 Plug @ ___ Ft. W/ ___ SX
Bottom Surface @ 280 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ ___ SX

WATER WELL ___ SX (Irr. Well ___ Pond ___)
Hauling ___

TECHNICIAN OG DATE

TYPE OF CEMENT 60-40-670 no box arc

STARTING TIME 10:30 (AM/PM) DATE 8-24-91

COMPLETION TIME 4 AM (AM/PM) DATE 8-25-91

CEMENT COMPANY Alawco