

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-23,336-00-00

LEASE NAME Huxman

WELL NUMBER 1-B

4290 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 14 TWP. 16 RGE. 25 (R) or (W)

COUNTY Ness

Date Well Completed 4-1-89

Plugging Commenced 4-1-89

Plugging Completed 4-1-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Raymond Oil Company, Inc.

ADDRESS One Main Place- Suite 900 Wichita, KS 67202

PHONE# (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-29-89 (date)

by Dick Cap (KCC District Agent's Name).

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4532

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

Formation	From	To	Size	Put in	Pulled out

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 6 1989  
 CONSERVATION DIVISION  
 STATE OF KANSAS

Describe in detail the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
 Bottom Plug: @1967' w/50 sacks cement thru drill pipe  
 Next Plug: @1200' w/80 " " " " " "  
 Next Plug: @260' w/50 " " " " " " 15 sacks cement in Rat Hole  
 Top Plug: @40' w/10 " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raymond Oil Company, Inc


STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~XXXXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 4<sup>th</sup> day of April, 1989

Dorothy M. Hague  
 Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: March 24, 1989  
 DATE COMPLETED: April 1, 1989

Raymond Oil Company, Inc.  
 HUXMAN #1-3  
 S/2 N/2 NW  
 Sec. 14, T16S, R25W  
 Ness County, Ks.

0 - 226' Surface Soil, Clay, Sand  
 226 - 1105' Shale & Shells  
 1105 - 1355' Shale  
 1355 - 1375' Sand  
 1375 - 1437' Red Bed  
 1437 - 1967' Anhydrite  
 1967 - 3519' Lime & Shale  
 3519 - 3861' Lime  
 3861 - 3979' Shale & Lime  
 3979 - 4197' Lime  
 4197 - 4242' Shale & Lime  
 4242 - 4320' Lime, Shale & Chert  
 4320 - 4399' Lime  
 4399 - 4532' Chert & Lime  
 4532' RTD

ELEVATION: 2557 K.B.

Surface Pipe: Set new  
 3-5/8", 20# pipe 6220'  
 w/130 sacks 60/40 pozmix  
 2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS  
 COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 4/1st day of April 1989.



RECEIVED  
 STATE CORPORATION COMMISSION

APR 5 1989  
 4-6-89  
 CONSERVATION DIVISION  
 Wichita, Kansas

*Notary M. Hogue*  
 Notary Public