


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 10 Twp. 16 Rge. 3 (E)W (W)
Location as "NE/CNW&SW" or footage from lines SE SW NW
Lease Owner W-D Oil Co., P. O. Box 296, Burlington, Colo.
Lease Name Thelander "C" Well No. 1
Office Address Burlington, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Feb. 19 19 59
Application for plugging filed June 11 19 68
Application for plugging approved June 12 19 68
Plugging commenced June 29 n 19 68
Plugging completed July 5 19 68
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back with sand to 3270'. Dumped 5 sacks of cement. Shot pipe off at 2736.20'. Pulled pipe and mudded hole to 300'. Set rock bridge from 300 to 290 feet. Dumped 25 sacks of cement. Finished mudding hole and dumped 10 sacks of cement at base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1968
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God!

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.

Subscribed and sworn to before me this 15th day of July, 19 68



z October 18, 1969 Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock,
 Wichita, Kansas

15-169-00178-00-00


COPY

Company - HOWARD KREBBS
 Farm - Thelander "C" No. 1

SEC. 10 T. 16 R. 3W
 SE SW NW

Total Depth. 3316'
 Comm. 2-11-59 Comp. 2-19-59
 Shot or Treated.
 Contractor. J. A. Melland
 issued. 4-10-59

County Saline
 KANSAS



CASING:
 8 5/8" 313' cem w/200 sx.
 5 1/2" 3280' cem w/50 sx.

Elevation. 1318' RB

Production. 30 BOPD

Figures Indicate Bottom of Formations.

| | |
|-----------------------|----------|
| surface soil & clay | 80 |
| shale & shells | 270 |
| shale, shells, gypsum | 280 |
| lime | 313 |
| Anhydrite | 340 |
| lime & shale | 600 |
| lime | 870 |
| lime & shale | 1040 |
| shale & shells | 1550 |
| shale & lime | 1650 |
| lime & shale | 2015 |
| sandy shale & shells | 2110 |
| shale | 2179 |
| lime & shale | 2600 |
| shale & lime | 2822 |
| Mississippi lime | 3035 |
| shale & lime | 3065 |
| shale | 3316 RTD |
| Total Depth | |

TOPS: SCOUT
 Maquoketa Dolomite 3310

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas