



15-169-00071-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 6, 1969

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: W-D Oil Company

Complete Address: c/o Bert Self, R. R. # 4, Hutchinson, Kansas 67501

Lease Name: Bloomberg Well No. 1

Location: NW NE NE Sec. 15 Twp. 16 Rge. 3 (E) (W) X

County: Saline Total Depth 3301' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3280' and cement hole with 5 sacks cement.

Fill hole with mud to 300'. Set rock bridge from 300' to 290' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent