

State of Kansas



15-169-00582-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 24, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 2 1966

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co.

has this

date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: P.O. Box 169, Russell, Kansas

Lease Name: Myers Well No. 2

Location: SE NE SW Sec. 15 Twp. 16 Rge. 3 (W) X

County Saline Total Depth 3324' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 3 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent