

State of Kansas



15-101-20111-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION SEP 13 1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Brandenburg Well No. C-1

Location: CSE-NW Sec. 16 Twp. 16 Rge. (E)(W) 28

County: Lane Total Depth 4438' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

228'--8 5/8" Surface casing, cement circulated with 175 Sx. Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

[Signature] Conservation Division Agent