



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

27 February 1982

RECEIVED  
STATE CORPORATION COMMISSION

MAR 2 1982

### VERBAL PERMIT FORM

(To be filed by Plugging Agent)

CONSERVATION DIVISION  
Wichita, Kansas

15-101-20,629-00-00

Dear Sir:

Mr. Alford Augustine of Murphy Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Oxford Exploration Co.

Complete Address: 1550 Denver Club Bldg. Denver Colo. 80202

Lease Name: Roberts Well No. 3-13

Location: C-SW-SW Sec. 3 Twp. 16 Rge. 28 (E) (41)

County: Lane Total Depth: 4430'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Augustine was instructed to plug the well as follows:

There is 335' of 8 1/2" surface casing cement circulated with 225 bbls of quick cement. The anhydrite was topped at 1999'. 1st plug at 1900' with 50 bbls of cement. 2nd plug 850' with 35 bbls of cement. 3rd plug push rubber plug to 325' and pumped 35 bbls of cement on top of it. 4th plug 40' to 0' with 10 bbls of cement. Then circulated 10 bbls of cement in rat hole. Cement used was common with 2 1/2" well

Very truly yours,

Paul Lutter  
Conservation Division Agent

(over)