

RECEIVED
STATE CORPORATION COMMISSION STATE CORPORATION COMMISSION

MAR 2 1982 CONSERVATION DIVISION AGENT REPORT

J D Kcc

CONSERVATION DIVISION
Wichita, Kansas

API Number

20629400-00
~~20240~~

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Offord Exploration Co.

Complete Address 1550 Denver Club Bldg, Denver Colo. 80202

Lease Name Roberts Well No. 3-13

Location C-SW-SW Sec. 3 Twp. 16 Rge. 28 (East)(West)

County Lane Total Depth 4430' ^{143.98}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Murphy Drilling Co Rig #15

Address 617 Union Center Bldg, Wichita Kansas 67202 License No. _____

Operation Completed: Hour: 7:30 PM Day: 27 Month: February Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 1999'. 1st plug at 1900' with 50 sby of cement. 2nd plug at 850' with 35 sby of cement. 3rd plug pushed rubber plug to 325' and pumped 35 sby of cement on top of it. 4th plug 40' to 0' with 10 sby of cement on solid bridge. Then they circulated 10 sby of cement in rat hole. The cement used was common with 2% gell + 3% C.C. and was pumped through drill pipe. The plugging was accomplished by Allied Cementing.

Amount of Surface Casing: 335' of 8 1/2" cement circulated with 225 sby quick cement

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

This was out of my area.

Signed: Paul Luthi
Conservation Division Agent

INVOICED

DATE 3-2-82

INV. NO. 9542-W