

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED CP-3
STATE CORPORATION COMMISSION
JUL 28 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-101-20,685-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name K. + E. Petroleum Inc.

Complete Address 100 S. Main, Suite 300 Wichita, Kansas 67202

Lease Name Lillotson Well No. 1

Location 380' FNL 2010' FEL Sec. 30 Twp. 16 Rge. 28 (East) (West)

County Lane Total Depth 4580'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Abrahamson Drilling Inc.

Address 801 Union Center, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 3:30 AM Day: 20 Month: July Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was at 2172'. The dakota was topped at 770' to 1280'. 1st plug at 2100' with 35 bbl of cement. 2nd plug at 1300' with 150 bbl of cement. 3rd plug at 380' with 35 bbl of cement 4th plug on solid bridge with 10 bbl of cement at 40' to 0'. They circulated 10 bbl cement in rat hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by firm cementing.

Amount of Surface Casing: 319' of 8 1/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

When he called for orders, I would haven't of had time to make the well.

Signed: Paul A. Luthi
Conservation Division Agent

INVOICED

DATE 7-29-82

INV. NO. 775-W