

15-101-19010-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Helmerich & Payne, Incorporated,

Complete Address: Box #558, Garden City, Kansas.

Lease Name Hartzog Well No. 1

Location CNW-^{SE}SW Sec. 25 Twp. 16 Rge. (E) (W) 28

County Lane Total Depth 4635

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Incorporated,

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 2:00PM Day 29 Month 8 Year 1965

The Above well was plugged as follows:

285'--8 5/8" Surface pipe, cement circulated with 200 Sx.
4598'--5 1/2" Production casing cemented with 125 Sx. Top of cement @ 3975'
(Temperature survey). Well plugged back to 4567'. Top perforations
from 4356' to 4360'.

Sanded well back to 4224' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 660' and pumped in 12 Sx. heavy gel mud. Pulled 5 1/2" to 600' and
displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 280' and displaced 20 Sx.
cement thru 5 1/2". Pulled 5 1/2". Set rock bridge @ 35' and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/31/65

INV. NO. 1725-W