

15-101-00053-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Helmerich & Payne, Incorporated,

Complete Address: Box #558, Garden City, Kansas.

Lease Name DeMand Well No. 1

Location CSW-NE Sec. 25 Twp. 16 Rge. (E) (W) 28

County Lane Total Depth 4748

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 10:30AM Day 4 Month 8 Year 1966

The Above well was plugged as follows:

286'--8 5/8" Surface pipe, cement circulated with 200 Sx.

4635'--5 1/2" Production casing cemented with 175 Sx. DV tool set @ 1020' with 225 Sx. cement to surface. Top perforations @ 4406'.

Sanded well back to 4375' and set 5 Sx. cement. Pushed plug to 300' set

15' rock bridge and filled 5 1/2" to bottom of cellar with cement using 38 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 8/10/66

INV. NO. 3432-d