

15-101-20101-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name O. A. Sutton,

Complete Address 800 Sutton Place, Wichita, Kansas.

Lease Name Templin Well No. 2

Location SW-SW Sec. 24 Twp. 16 Rge. (E) (W) 28

County Lane Total Depth 4670'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 11:00 AM Day 16 Month 4 Year 1974

The above well was plugged as follows:

318'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement
thru DP from 1000' to 675'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru
DP from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/23/74

INV. NO. 8976-W