

15-101-20061-00-00

Form CP-3
Rev. 6-4-68

KANSAS

70

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Ware Well No. 1

Location 800' FNL & 400' FWL of NW/4 Sec. 22 Twp. 16 Rge. (E) (W) 28

County Lane Total Depth 1494'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:45 AM Day 4 Month 6 Year 1973

The above well was plugged as follows:

194'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Cu. Ft. cement
thru DP from 925' to 600'. Pulled DP to 215' and displaced 30 Cu. Ft. from 215' to
140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 6/7/73
INV. NO. 7466-22