

15-101-20045-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Incorporated,
Complete Address 7701 E. Kellogg, Wichita, Kansas.
Lease Name Tillston Well No. C-1
Location NW-SE-NW Sec. 20 Twp. 16 Rge. (E) (W) 28
County Lane Total Depth 4607'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address P. O. Box #405, Chase, Kansas. License No. 624
Operation Completed: Hour 3:00 PM Day 29 Month 1 Year 1974

The above well was plugged as follows:

265'--8 5/8" Surface casing, cement circulated.
4246'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to
4211'. Casing collapsed @ 2800'. Rotary mud standing in 5 1/2" casing @ 1200'.
Shot and pulled 5 1/2" casing @ 1240' and squeezed well initially with 3 sacks hulls and
followed with 15 Sx. cement then 15 sacks gel and followed with 60 Sx. cement then
2 sacks hulls, 5 sacks gel and finally 25 Sx. cement. Final shut-in pressure-500#.
(Mudding and cementing operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/5/74
INV. NO. 8522-W

Signed: H. L. Oriskany
Well Plugging Supervisor