

*Copy of letter  
to be filed*

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM (P-1)

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15 - 101-20,145 -00-01 (of this well)

Lease Owner Voyager Petroleum, Inc.

Address 110 16th Street, Suite 800, Denver, CO 80202 - Phone (303) 629-1447

Lease (Farm Name) Ruby Ryan Well No. 1

Well Location C SW SE Sec. 14 Twp. 16S Rge. 28W ~~(28W)~~ ~~(16S)~~

County Lane Total Depth 4450' Field Name \_\_\_\_\_

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A \_\_\_\_\_

Well Log attached with this application as required \_\_\_\_\_

Date and hour plugging is desired to begin At discretion of plugging agent and contractor  
to be accomplished by 2/01/84.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Layle L. Robb (303) 629-1447 Address 110 16th Street, #800, Denver, CO 80202

Plugging Contractor Clarke Corporation License No. 583

Address 107 W. Fowler, Medicine Lodge, Kansas 67104 (316) 886-5665

Invoice covering assessment for plugging this well should be sent to:

Name Voyager Petroleum, Inc. - Attention: Layle L. Robb

Address 110 16th Street, Suite 800, Denver, CO 80202

and payment will be guaranteed by applicant or acting agent.

Signed: Layle L. Robb Layle L. Robb  
Applicant or Acting Agent

Date: December 13, 1983

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1983

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas



15-101-20145-00-01

JOHN CARLIN  
MICHAEL LENNEN  
R. C. (PETE) LOUX  
PHILLIP R. DICK  
JUDITH MCCONNELL  
BRIAN J. MOLINE

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE SECRETARY  
GENERAL COUNSEL

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

January 9, 1984

THIS NOTICE

APR 7 1983

EXPIRES

WELL PLUGGING NOTICE

Ruby Ryan #1  
C SW SE  
Sec.14-16s-28W  
Lane County

Voyager Petroleum Inc.  
110 16th St. Suite 800  
Denver CO 80202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Yours very truly,

Carol J. Larson, Administrator

Please submit your proposal for plugging the above captioned well to

Dodge City District#1 302 West McArton Dodge City KS 67801

seven days prior to plugging the well (KAR-82-3-113)

15-101-20145-00-01

VOYAGER



PETROLEUMS, INC.

December 14, 1983

State of Kansas  
Corporation Commission  
Conservation Division  
200 Colorado Derby Building  
Wichita, KS 67202

Gentlemen:

Attached for your approval is Well Plugging Application Form (CP-1) requesting approval for the plug and abandonment of Voyager Petroleum, Inc.'s #1 Ruby Ryan well located in the SW SE Section 14, T16S, R28W, Lane County, Kansas. The well will be plugged and abandoned in the following manner.

- 1.) The 4½" OD, 10.5# production casing will be filled with 18 sacks sand from 4396' KB (PBD) to 4200' KB (perfs at 4294'-4299' and 4303'-4308') and a 5 sx cement plug will be spotted on the sand for a plug from 4200' to 4133'.
- 2.) The 4½" OD production casing will be ripped at its free point and recovered (estimated casing recovery of about 2000 feet).
- 3.) A surface plug consisting of the following will be pumped down the 8-5/8" surface casing (landed at 258' KB) and displaced 5 feet below ground level.
  - Top plug
  - 6 sx hulls
  - 20 sx gel
  - 75 sx cement
  - 20 sx gel
  - 1 sx hulls
  - plug
  - 100 sx cem w/4% gel & 3% CaCl<sub>2</sub>

Voyager Petroleum, Inc. would like to commence with this work shortly after the first of the year.

Very truly yours,  
VOYAGER PETROLEUMS, INC.

Layle L. Robb  
Production Manager

LLR/kr

cc: Clarke Corporation  
American Petroleum Company of Texas - Dallas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1983

CONSERVATION DIVISION  
Wichita, Kansas