

15-101-20859-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY _____ LANE _____ SEC. 21 TWP. 16S RGE. 28W E/W
 Location as in quarters or footage from lines:
 SE SW

Lease Owner KRM PETROLEUM CORPORATION
 Lease Name WARE Well No. 2-21
 Office Address 1900 GRANT STREET, SUITE 300, DENVER, COLO. 80203
 Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
 Date Well Completed 10:30 P.M., 10-10-83
 Application for plugging filed 10-18-83
 Plugging commenced 8:30 P.M., 10-10-83
 Plugging completed 10:30 P.M., 10-10-83
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well PAUL LUTHI
 Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	335	J-55	24 Jts.	

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Well was plugged as follows:

175 sks of 60/40 pos., 2% gel, 3% cc. Plugs were staged at:
 50 sks at 2120', 40 sks at 1600', 50 sks at 280', 10 sks at 40' to surface,
 15 sks in rat hole and 10 sks in mouse hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HALLIBURTON NESS CITY, KS.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
KRM PETROLEUM CORPORATION (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]
 453 S. WEBB ROAD, BOX 18611
 WICHITA, (Address) KANSAS 67207

SUBSCRIBED AND SWORN TO before me this 18TH day of OCTOBER, 19 83

[Signature]
 KATHLEEN G. QUINN Notary Public.

My Commission expires: MARCH 20, 1987



RECEIVED
 STATE CORPORATION COMMISSION
 OCT 20 1983
 CONSERVATION DIVISION
 Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

15-101-20859-00-00

WELL LOG



WELL NAME: WARE #2-21

WELL LOCATION: SE SW

21-16S-28W, LANE CO., KS.

COMMENCED: 5:45 P.M. 10-2-83

COMPLETED: 10:30 P.M. 10-10-83

OPERATOR: KRM PETROLEUM CORPORATION

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

CASING RECORD: _____

8 5/8" set at 335'

FORMATION:

FROM:

TO:

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>
Sand-Soil and Shale	0	345'
Shale	345'	1280'
Anhy. Shale	1280'	1294'
Shale	1294'	1296'
Sand and Shale-Red Bed	1296'	1700'
Sand	1700'	1830'
Shale and Red Bed	1830'	2770'
Lime and Shale	2770'	4591'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
SE SW, 21-16S-28W, LANE CO., KANSAS TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.
Arnie Little
ARNIE LITTLE
VICE-PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 18TH DAY OF OCTOBER, 1983

MY APPOINTMENT EXPIRES IN
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Appt. Exp. 3-20-87

MARCH 20, 1987

Kathleen G. Quinn
KATHLEEN G. QUINN
NOTARY PUBLIC