

15-101-20057-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 20 TWP. 16 SRGE. 28 E/W
 Location as in quarters or footage from lines:
75' South of NW-SE-NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Thunderbird Drilling, Inc.
 Lease Name Tillotson "C" twin Well No. 1
 Office Address P. O. # 97 Ellinwood, Kansas 67526
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed 5-17-1973
 Application for plugging filed 7-12-82
 Plugging commenced 10-6-82 2 P.M.
 Plugging completed 10-6-82 4:30 P.M.
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation LKC Depth to top 3937 bottom T.D. 3970

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	265	none
				5 1/2	4091	none

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. No casing pulled 5 1/2" casing was

cemented to surface thru stage collar @ 2165 w/ 450 sacks
LKC perforated from 3938 to 3945

Allied Cementing mixed & pumped 2 sacks hulls, 35 sacks cement,
18 sacks gel, 5 1/2" wiper plug & 130 sacks cement

Finished pumping @ 4:30 P.M. w/300 # SIP

Cement was 50/50 Posmix with 4 % gel & 3 % CCL

plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Barton, ss.


Maynard E. Weber (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Maynard E. Weber
P.O. # 97, Ellinwood, Ks. 67526
 (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of Oct, 1982

Trevlyn Detmer
 Notary Public.
 STATE CORPORATION COMMISSION

My Commission expires _____



OCT 12 1982

CONSERVATION DIVISION
 Wichita, Kansas