


15-135-20829-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec. 25 Twp. 16S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines C/SW NE

Lease Owner Patrick Petroleum Corporation

Lessee Name Nelson Well No. 1

Office Address 330 Page Court, 220 West Douglas, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 20 19 73

Application for plugging filed December 20 19 73

Application for plugging approved December 20 19 73

Plugging commenced December 20 19 73

Plugging completed December 20 19 73

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4545 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	284.76'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 745' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 7:30 P. M. December 20, 1973.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 28 1973  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp, President  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 21st day of December, 1973.  
Elaine H. Taylor Notary Public.

My commission expires December 14, 1977



D R I L L E R S      L O G

#1 Nelson

CASING RECORD:  
279.76' of new 8-5/8"  
surface casing.

COMPANY: Patrick Petroleum Corporation

DESCRIPTION: C/SW NE  
Section 25-16S-25W  
Ness County, Kansas

CONTRACTOR: Strata Drilling, Inc.

TOTAL DEPTH:  
4545'

COMMENCED: December 9, 1973

COMPLETED: December 20, 1973

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale w/Sand Streaks	0	295	Ran 279.76' of new 8-5/8" surface casing; set and cemented at 284.76' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 1:30 A. M. December 10, 1973.
Shale	295	345	
Shale w/Sand Streaks	345	1175	
Shale & Sand	1175	1902	
Shale w/Lime Streaks	1902	2560	
Lime & Shale	2560	3960	
Lime	3960	4050	
Lime & Shale	4050	4238	
Lime	4238	4340	
Lime & Shale	4340	4440	
Lime	4440	4545	

ROTARY TOTAL DEPTH: 4545'

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 28 1973  
CONSERVATION DIVISION  
Topeka, Kansas

Ran electric log

D. & A.

Plugged hole as follows: Plugged at 745' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 7:30 P. M. December 20, 1973.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 21st day of December, 1973.

My Commission Expires:

December 14, 1977

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

