


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec. 25 Twp. 16 Rge. 25 (W)  
Location as "NE/CNW/SE" or footage from lines C NW/4 SW/4  
Lease Owner Sterling Drilling Company  
Lease Name Flax Well No. 1  
Office Address Box 129, Sterling, Kansas 67579  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 26 1967  
Application for plugging filed January 26 1967  
Application for plugging approved January 26 1967  
Plugging commenced January 26, 10:00 a.m. 1967  
Plugging completed 3:15 p.m. January 26 1967  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 1986 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	NONE					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 1635', 50 sacks HA5 through drill pipe at 1635'.  
Heavy mud to 1535', 150 sacks 50 X50 Pozmix #1 with 4% gel through drill pipe at 1535'.  
Heavy mud to 450', 150 sacks 50 X 50 Pozmix #1 with 4% gel from 450' to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 2 1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company  
Address Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
F. A. Wuellner, Sec.  
Box 129, Sterling, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of January, 1967

BERNARD LAUDERMILK, Notary Public  
Commission Expires January 22, 1970  
My commission expires

Bernard Laudermilk  
Bernard Laudermilk, Notary Public.



STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG ----- PLAX #1  
LOCATED: C NW SW Section 25-16S-25W, Ness County, Kansas

OWNER: Sterling Drilling Company, et al  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 24, 1967  
COMPLETED: January 26, 1967

ROTARY TOTAL DEPTH: 1986'

LOG

CASING RECORD

0 - 180 Sand & Clay  
180 - 320 Clay & Shale  
320 - 1700 Shale & Sand  
1700 - 1916 Shale  
1916 - 1948 Anhydrite  
1948 - 1986 Shale T.D.

Plugged with 50 sacks HA5 at 1635'  
through drill pipe; 150 sacks 50 - 50  
Pozmix #1 with 4% gel at 1535'; 150  
sacks 50 - 50 Pozmix #1 with 4% gel  
from 450' to surface. Completed at  
3:45 p.m. by Howco. Plugger, Leo  
Massey.

RECORDED  
INDEXED  
FEB 2 1967  
CONCRETE DIVISION  
STERLING, KANSAS