

15-101-00018-00-01
WELL PLUGGING RECORD

NORTH

A 4x4 grid with a small black dot in the top-right cell.

Lane _____ County. Sec. 16 Twp. 16S Rge. 28W (E) _____ (W) _____
Location as "NE/CNW¼SW¼" or footage from lines _____ Center NW NE
Lease Owner Courtney B. Davis
Lease Name Nimocks Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) old well worked over
Date well completed February 25, 1937 19_____
Application for plugging filed January 12, 1952 19_____
Application for plugging approved January 12, 1952 19_____
Plugging commenced 2-20-52 19_____
Plugging completed 2-27-52 19_____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Sanded hole from 4533' to 4035' and ran 6 sacks of cement. Mudded hole to 250', set 10' rock bridge and ran 25 sacks of cement. Mudded hole to 20' and ran 15 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor.....West Supply Company
Address.....Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature)

day of

SUBSCRIBED AND SWORN TO before me this

My commission expires

23-8390-s 6-51-20M

UGGING
FILE SEC 16 T 16 R 28W
BACK PAGE 137 LINE 21

WELL LOG

J. E. TRIGG.

OKLAHOMA CITY, OKLAHOMA

NIMOCKS #1 : Center of NW $\frac{1}{4}$ of NE $\frac{1}{4}$ Sec 16, Twp 16S, RGE. 28W
Lane County, Kansas

Elevation :
Started : December 17, 1937.
Completed : February 25, 1937

Surface	0 - 108	Shale	3438 - 3485
Lime Shells & Shale	108 - 120	Lime	3485 - 3578
Sandy Lime	120 - 227	Shale	3578 - 3587
Sandy Shale	227 - 415	Lime	3587 - 3694
Blue Shale	415 - 505	Shale	3694 - 3703
Sandy Shale	505 - 560	Lime	3703 - 3955
Shale & Shells	560 - 680	Shale	3955 - 3980
Sand	680 - 768	Lime	3980 - 4038
Shale & Shells	768 - 785	Shale	4038 - 4045
Sandy Shale	785 - 930	Lime	4045 - 4070
Shale	930 - 1120	Shale	4070 - 4083
Shale & Shells	1120 - 1310	Lime	4083 - 4090
Sand	1310 - 1320	Shale	4090 - 4098
Shale & Shells	1320 - 1375	Lime	4098 - 4460
Green Shale	1375 - 1510	Conglomerate	4460 - 4485
Lime	1510 - 1519	Lime	4485 - 4695
Shale & Shells	1519 - 1551	Chert & Lime	4695 - 4797
Green Shale	1551 - 1830	Lime	4797 - 4910
Shale & Shells	1830 - 1949	Chert & Lime	4910 - 4953
Shale	1949 - 2070	Lime (porous)	4953 - 5121
Lime (hard)	2070 - 2192		
Shale & Shells	2192 - 2237		
Lime	2237 - 2344		
Shale & Shells	2344 - 2480		
Salt	2480 - 2500		
Lime	2500 - 2520		
Shale & Shells	2520 - 2590		
Lime	2590 - 2680		
Shale & Shells	2680 - 2725		
Sandy Lime	2725 - 2783		
Lime	2783 - 2862		
Sandy Shale	2862 - 2923		
Shale & Shells	2923 - 2986		
Lime	2986 - 3138		
Shale & Shells	3138 - 3185		
Lime	3185 - 3292		
Shale & Shells	3292 - 3438		

Set 108 feet of new 40# 12 $\frac{1}{2}$ " casing
and cemented with 125 sacks cement

I, J. E. Trigg, of Oklahoma City, Oklahoma, do hereby certify that the above and foregoing is a true and correct copy of the well log of the Nimocks #1 well as reflected by my records.

/s/ J. E. Trigg

Subscribed and sworn to before me this 27 day of
February, 1937.

/s/ Clara Cawthon

My Commission expires 11-13-38

