

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Nimocks Johnson

WELL NUMBER 41

____ Ft. from S Section Line

____ Ft. from E Section Line

SEC. 16 TWP. 6S RGE. 28W X(E) or (W)

COUNTY Lane

Date Well Completed 9-30-72

Plugging Commenced 4-19-90

Plugging Completed 4-23-90

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water Suite #300 Wichita, KS. 67202

PHONE#(316 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4525'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 161' | none |
| | | | | 5 1/2" | 4523' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Sanded bottom to 3820' dumped 5 sacks cement. Shot pipe @1800', 1700', 1600', 1500', 1300', 1100'. Pumped 5 sacks gel, 80 sacks cement 1/4# flow seal per sacks shut in @550 ft. and pumped 70 sacks cement. Pumped down long string pumped one hull and 100 sacks cement circulated cement to top. Down surface pumped one hull and
 (If additional description is necessary, use BACK of this form.) 100 sacks cement.

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, KS. 67524

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

JUL 10 1990

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *[Handwritten Signature]*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 13 day of July, 19 90

[Handwritten Signature: Irene Herzberg]
Notary Public

My Commission Expires: _____

