

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Lane SEC. 15 TWP. 16 RGE. 28 W
Location as in quarters or footage from lines:

2310' FNL & 330' FWL

2310'
FNL

X			

330' FWL
Locate Well
correctly on above
Section Platt.

Lease Owner TXO Production Corp. (formerly Texas Oil & Gas Corp.)

Lease Name Dixon "F" - 1 Well No. 1

Office Address 200 W. Douglas, Suite 300, Wichita, Kansas 67202

Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole

Date Well Completed October 14, 1981

Application for plugging filed October 14, 1981, verbally

Plugging commenced 6:30 p.m. October 13, 1981

Plugging completed 1:15 a.m. October 14, 1981

Reason for abandonment of well or producing formation

Dry Hole *CM*

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation N/A Depth to top N/A bottom N/A T.D. N/A

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8" 24lb	587'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Plugged with 50-50 pozmix - 6% gel.

- Set 1st Plug @ 900' with 70 sacks
- Set 2nd Plug @ 500' with 40 sacks
- Set 3rd Plug @ 40' with 10 sacks
- 5 sacks rathole
- 5 sacks mousehole

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1981

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

C. K. Morrison (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) *CK Morrison*

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of October, 19 81

Suzanne P. Graef
Notary Public.

My Commission expires: Oct. 26, 1981



CONTRACTOR'S WELL LOG

OPERATOR: TXO Production Corp.
 CONTRACTOR: KANDRILCO, Ltd.
 WELL NAME: Dixon F #1
 LOCATION: 2310' FNL, 330' FWL Sec. 15, T16S-R28W,
 Lane County, KS
 API NO.: 15-101-20,561
 COMMENCED: October 5, 1981
 COMPLETED: October 14, 1981

Drilled 607' of 12 1/4" hole. Set 587' of new 8 5/8" 24# casing at 587' with 225 sacks light weight and 125 sacks of common cement - 2% gel, 3% CaCl. Cement did circulate to surface. Plug was down at 2:00 p.m., October 6, 1981.

<u>FORMATION</u>	<u>TOP'</u>	<u>BOTTOM'</u>
Sand and Shells	0	607
Shells and Shale	607	1607
Shale and Lime	1607	2800
Lime and Shale	2800	3400
Lime, Chert and Shale	3400	4000
Lime and Chert	4000	4635

RTD 4635'. Plugged to abandon. Plugged with 50-50 Pozmix, 6% gel. Set 70 sacks at 900', 40 sacks at 500', 10 sacks at 40', 5 sacks rathole and 5 sacks mousehole. Plugging complete at 1:15 a.m., October 14, 1981.

STATE OF KANSAS, COUNTY OF SEDGWICK, SS:

I, C. K. Morrison, President, KANDRILCO, Ltd., do hereby state that the above is a true and correct copy of the Driller's Log for the TXO Production Corp. Dixon F #1 located in Lane County, Kansas.

RECEIVED
STATE CORPORATION COMMISSION

KANDRILCO, Ltd.

OCT 21 1981

C. K. Morrison

CONSERVATION DIVISION
Wichita, Kansas

C. K. Morrison, President

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, as of this 21st day of October, 1981.

Suzanne P. Graef
Suzanne P. Graef - Notary Public

My Commission expires: October 26, 1981