

15-101-20977-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 10 TWP. 16 S RGE. 28W E/W
 Location as in quarters or footage from lines:
 1980 FSL & 1980 FEL of section

		X	

Locate Well
 correctly on above
 Section Platt.

Lease Owner S & W Drilling Co.
 Lease Name Dixon Well No. 10-10
 Office Address P O Box 132, Oberlin, Ks. 67749
 Character of Well (Completed as Oil, Gas or Dry Hole): D&A
 Date Well Completed 6-14-84
 Application for plugging filed 6-15-84
 Plugging commenced 7:00 PM 6-14-84
 Plugging completed 1:15 AM 6-15-84
 Reason for abandonment of well or producing formation D&A rotary

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey
 Producing formation none Depth to top bottom T.D. 4470

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.
Surface Sand-Ft Hays	Im water	0	280	8 5/8	307	0

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set. hole full of mud

1 st plug at 2030 w/ 50 sx.
2nd plug @ 1000 w/ 50 sx.
3rd plug @ 700 w/ 50 sx.
4th plug @ 330 w/ 40 sx.
solid bridge pushed to 40' w/ 10 sx on top, 15 sx in rathole, cement used 215 sx. 60/40
poz w/ 2% gel & 3% CC by Sun

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling Co. 801 Union Center Wichita, Ks.

STATE OF KANSAS COUNTY OF DECATUR, ss.

James L Reeves (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log-of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James L Reeves
Oberlin KS
 (Address)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 18 1984

SUBSCRIBED AND SWORN TO before me this 15th day of JUNE, 19 84

Wiley L. Beal
 Notary Public.

My Commission expires: 12/22/86

