


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Lane _____ County. Sec. 9 Twp. 16S Rge. 28
Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Dane G. Hansen Trust
Lease Name Walton Well No. 1
Office Address Logan, Kansas 67646
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 9/16 1977
Application for plugging filed 9/16 1977
Application for plugging approved 9/16 1977
Plugging commenced 9/16 1977
Plugging completed 9/16 1977

Reason for abandonment of well or producing formation
Too low structurally

If a producing well is abandoned, date of last production
1977

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 47'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263.73'	None

Describe in detail the manner in which the well was plugged, indicating where the mud flu-
was placed and the method or methods used in introducing it into the hold. If cement or oth-
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled with heave mud to 750'. Set plug.
Put in 70 sacks common cement. Filled
with heave mud to 240'. Set plug. Put in
20 sacks cement. Filled with heavy mud up
to 40'. Set plug. Filled to top with 10
sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO.
1107 Douglas Bldg., Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.
G F GALLOWAY (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) G F GALLOWAY 1107 Douglas Bldg.
(Address)

Subscribed and Sworn to before me this 21st day of September 1977

My commission expires March 3, 1980

Debra L Heersche
DEBRA L HEERSCHÉ Notary Public.



KANSAS DRILLERS LOG

API No. 15 — 101 — 20249-00-00
County Number

Operator
DANE G HANSEN TRUST

Address
LOGAN, KANSAS 67646

Well No. 1 Lease Name WALTON

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor C-G DRILLING CO. Geologist JERRY JESPERSEN


Spud Date 9/7/77 Total Depth 4473' P.B.T.D.

Date Completed 9/16/77 Oil Purchaser

S. 9 T. 16S R. 28 E
Loc. NE NE NE

County LANE

640 Acres
N



Locate well correctly

Elev.: Gr.

DF. KB 2602'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4"	8 5/8"	28#	263.73'	COMMON	150	2% GEL 3% CA CL

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1977

CONSERVATION DIVISION
Wichita, Kansas

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)		
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DANE G HANSEN TRUST		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: DRY HOLE	
Well No. 1	Lease Name WALTON		
S <u>9</u> T <u>16S</u> R <u>28</u> ^{EX} _W		101	
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
SHALE & SAND	0	1480	
SHALE	1480	1570	
SAND	1570	1795	
RED BED	1795	2020	
ANHYDRITE	2020	2072	
RED BED & SHALE	2072	2290	
SHALE & SHELL	2290	2560	
LIME & SHALE	2560	3900	
LIME & RTD	3900	4473	
DST #1 4054-4090' 30-30-30-30 REC 275' GIP, 60' OIL, 30' OCMW, 550' WSOCMW, 425' MSW, IBHP 1136 FBHP 1094, IFP 41, FFP 491 DST #2 4309-4352 30-30-30-30 Weak blow f/10 min. REC 10' MUD IBHP 99#, FBHP 99, IFP 99, FFP 99.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<i>Debra Heersche</i> DEBRA HEERSCHE Signature OFFICE MANAGER Title 9/23/77 Date		