

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24669-00-00
Spot: S2N2NW Sec/Twnshp/Rge: 18-13S-19W
4290 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DISNEY Well #: 1
County: ELLIS Total Vertical Depth: 3833 feet

Operator License No.: 5798
Op Name: WEILERT, MICHAEL D. DBA MICHAEL
Address: 866 230TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		160 SX
PROD	4.5	3818		550 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2012 10:00 AM
Plug Co. License No.: 34519 Plug Co. Name: DOUBLE DRUM WELL SERVICE LLC
Proposal Rcvd. from: CURTIS WEILERT Company: MICHAEL D WEILERT OIL CO. Phone: (785) 656-3540

Proposed Plugging Method: Ordered - 260 sacks 60/40 poz mix with 4% gel; 500 # hulls; 8 sacks gel.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2012 12:50 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Double Drum Well Service RIH with tubing to 3605' Swift rigged to tubing & mixed & pumped 8 sacks gel followed by 50 sacks 60/40 poz mix with 200 # hulls mixed in.
Pulled tubing to 1850' Swift rigged to tubing & mixed & pumped 115 sxs 60/40 poz mix with 300# hulls mixed in to circulate cement to pit area.
Pulled tubing topped off 4.5" CSG with 25 sacks. Hole was standing full.
Rigged to 8.625" CSG with a swedge & pumped 15 sacks with 300 # PSI & 300 # SIP.

Perfs:

Top	Bot	Thru	Comments
3686	3698		

Remarks: SWIFT CEMENTING SERVICES TICKET # 21258

Plugged through: TBG

RECEIVED
MAR 20 2012

KCC WICHITA

District: 04

Signed Patrick Staab
(TECHNICIAN)

CM

MAR 15 2012

Form CP-2/3

✓ 3/27/12