

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25123-00-00
Spot: SENENW Sec/Twnshp/Rge: 8-14S-19W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GOTTSCHALK Well #: 1-D
County: ELLIS Total Vertical Depth: 3869 feet

Operator License No.: 5798
Op Name: WEILERT, MICHAEL D. DBA MICHAEL
Address: 866 230TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	202		150 SX
T1	2.875	3864		
PROD	5.5	3864		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2012 1:00 PM
Plug Co. License No.: 34519 Plug Co. Name: DOUBLE DRUM WELL SERVICE LLC
Proposal Rcvd. from: CURTIS WEILERT Company: MICHAEL D WEILERT OIL CO. Phone: (785) 656-3540

Proposed Plugging Method: Ordered- 350 sacks 60/40 poz mix 4% gel; 500 # hulls; 10 sacks gel
ALT-2 completed
High fluid level in well bore

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2012 5:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Double Drum Well Service RIH with tubing to 3763', Swift rigged to tubing & mixed & pumped 10 sxs gel, followed by 75 sxs cement with 300 # hulls mixed in.
Pulled tubing to 2050' Swift rigged to tubing & mixed & pumped 205 sxs with 200 # hulls mixed into circulate cement to pit area.
Pulled tubing topped of 5.5" CSG with 40 sxs. Hole was standing full.
Rigged to 8.625" CSG with a swedg and pumped 5 sxs to pressure. Blew a small hole under well head no shut in pressure.

Perfs:


Top	Bot	Thru	Comments
3864	3869		PERF
3860	3869		

Remarks: SWIFT CEMENTING SERVICES TICKET # 21451

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

MAR 14 2012

Form CP-2/3

✓ 3/27/12

RECEIVED

MAR 20 2012

KCC WICHITA